General Disclaimer


One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some
 of the material. However, it is the best reproduction available from the original
 submission.

Produced by the NASA Center for Aerospace Information (CASI)

DRL : 10. 188 DRD No. SE-2 JPL Contract No. 956334

FR-60038







DRL No. 188 DRD No. SE-2

A Final Report for: BLOCK V DOCUMENTATION AND SOLAR MODULES

February 28, 1985

Submitted to:

JET PROPULSION LABORATORY

4800 Oak Grove Drive

Pasadena, California 91103

Submitted by:
SPIRE CORPORATION
Patriots Park
Bedford, Massachusetts 01730

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately-owned rights.

ABSTRACT

Design and fabrication of Spire Corporation's Block V photovoltaic flat-plate module is reviewed. These modules exhibited power of about 70 watts under standard test conditions. Results of performance and environmental testing are provided.

TABLE OF CONTENTS

Section		Page
i	INTRODUCTION	1-1
2	MODULE DESIGN	2-1
	2.1 Module Dimensions	2-1
	2.2 Encapsulation and Edge Sealing Systems	2-3
	2.3 Electrical Connections	2-5
	2.4 Solar Cells	2-6
	2.5 Module Circuit Diagram	2-6
	2.6 Rooftop Mounting	2-6
3	PROGRAM PROGRESS	3-1
4	TEST DATA	4-1
	4.1 Tests and Inspections	4-1
	4.2 Environmental Tests	4-1
5	NEW TECHNOLOGY	5_1

LIST OF ILLUSTRATIONS

Figure		Page
1-1	Interface Control Drawing Illustrating Rooftop Mounting	. 1-2
1-2	Interface Control Drawing Illustrating Essentials of the Module Design	. 1-3
2-1	Panel Assembly Drawing	2-2
2-2	Cross Section of the Solar Module Encapsulation System	2-3
2-3	Solar Module Encapsulation System with Gasket and Perimeter Glide	. 2-4
2-4	Typical 5.2 kW Array	2-5
2-5	Solar Cell and Photo Mask Pattern Detail	. 2-7

LIST OF TABLES


Number	•											P	age
3-1	Nominal Module Performance at 80 mW/cm ²		•	•	•	•	•	•	•	•	•		3-1
3-2	Nominal Operating Performance at 100 mW/cm ²	•	•	•	•		•	•	•	•	•	•	3-l
4-1	Performance Data for Delivered Modules	•	•	•		•	•	•	•	٠	•	•	4-1
4-2	Summary of Electrical Performance		_			_			_		_		4-2

SECTION I


This is the final design report for JPL Contract 956334, "Block V Documentation and Solar Cell Modules." In this work Spire delivered ten high performance flat-plate modules. This report reviews their design, fabrication and testing.


Figure 1-1 replicates the interface control drawing, which indicates the manner in which a 5 kW array is mounted on a residential structure. In Figure 1-2, we show the interface control drawing which illustrates the module construction. These drawings serve to acquaint the reader with the general module design. In Section 2 of this report, we provide additional data on the module design and fabrication.


The Spire Block V modules were formed from cells having an average efficiency of 13%. Module efficiency at 25°C was 10%. Further information on performance and testing may be found in Sections 3 and 4.



ROOFTOP MOUNTING







SECTION 2

This section reviews in detail the module design and construction. Included is a discussion of the solar cell and encapsulation system employed.

2.1 MODULE DIMENSIONS

The overall dimensions of the Spire Block V module are $23.44 \pm .07$ inches by $44.63 \pm .07$ inches, as shown by the panel assembly drawing in Figure 2-1. The design minimizes edge shadowing for angles of up to 45° . Solar cell packing factor for this design is 75.7%. It can be seen from Figure 2-1 that the module consists of 72 silicon solar cells. Maximum weight of the module is 16 lbs.





FIGURE 2-1. PANEL ASSEMBLY DRAWING



2.2 ENCAPSULATION AND EDGE SEALING SYSTEMS

The encapsulation system is based on a glass superstrate approach utilizing ethylene vinyl acetate (EVA) adhesive and a laminated Tedlar back cover. Figure 2-2 illustrates a cross-section of the encapsulation system. A fiberglass scrin, is employed beneath the back cover for added mechanical strength. All modules were laminated in the SPI-LAMINATOR 240. Figure 2-3 illustrates the edge seal and gasket. No frame was used in this design.




FIGURE 2-2. CROSS SECTION OF THE SOLAR MODULE ENCAPSULATION SYSTEM




FIGURE 2-3. SOLAR MODULE ENCAPSULATION SYSTEM WITH EDGE SEAL AND GASKET

2.3 ELECTRICAL CONNECTIONS

Electrical connections are made to the module by a prefabricated wire harness. Location of the output terminals is shown in the panel assembly drawing (Figure 2-1). A typical 5.2 kW array is shown in Figure 2-4.

ELECTRICAL: 12 S x 8 P. Vno 180 V DC.

MECHANICAL: EVERY OTHER ROW

MOUNTED THE SAME.

ADJACENT ROWS INVERTED 180°.




FIGURE 2-4. TYPICAL 5.2 kW ARRAY

2.4 SOLAR CELLS

The solar cells used in the Spire Block V module are made from four inch p-type Czochralski wafers with a nominal resistivity of between 2 and 10 ohm-cm. The junctions are formed by ion implantation of phosphorus and back surface fields are formed by ion implantation of boron, resulting in an n⁺pp ⁺ structure. Nominal thickness of the cells is 20 mils.

Cell metallization comprises lift-off patterned Ti-Pd-Ag. The conductivity of the front grid is increased by electroplating silver onto the contact. All cells have a TiO₂ antireflection coating applied by evaporation.


Figure 2-5 illustrates the grid pattern and overall dimensions of the cell. A parallel busbar interconnect is used to obtain crack tolerance and low contact resistance. Average cell performance was 12.7%.


2.5 MODULE CIRCUIT DIAGRAM

The module circuit diagram is illustrated by a detail in Figure 1-2. It consists of six-cell series strings. The strings are connected in a network of 2 parallel 36 cell strings cross-tied every 6th cell. Three by-pass diodes are connected in series with each other. Each is in parallel with a twelve-cell string, as illustrated in the figure.

2.6 ROOFTOP MOUNTING

Details of mounting were provided in the interface control drawing in Figure 1-1.





SECTION 3 PERFORMANCE

Tables 3-1 and 3-2 list the nominal performance of the Block V module. These were estimated, based on design experience, at the time of the design review.

TABLE 3-1
NOMINAL MODULE PERFORMANCE AT 80 mW/cm²

Nominal operating cell temperature	49°C
Nominal operating voltage	15 V
Average power	54.4 W
Peak power	78.0 W
Average efficiency	10.1%
Peak efficiency	11.6%
Average operating current	3,63 A
Peak operating current	5.20 A

TABLE 3-2

Nominal operating cell temperature	56°C
Nominal operating voltage	15 V
Average power	68 W
Peak power	97.5 W
Average efficiency	10.1%
Peak efficiency	11.6%
Average operating current	4.5 A
Peak operating current	6.5 A

The packing density of the cells in the Block V module is 75.7%. The temperature coefficient used to calculate NOCT performance is -0.335 W/°C. The above values for nominal power were based on experience gained through development of the Block IV solar modules.

SECTION 4 TEST DATA

Test data for the modules delivered in the program are replicated in Table 4-1. Average module efficiency was 10.2% (100 mW/cm², 25°C) as measured by JPL.

TABLE 4-1
PERFORMANCE DATA FOR DELIVERED MODULES

Serial Number	Spire Pmax(W)	JPL Pmax(W)	
002	74.9	70.8	
003	71.3	70.7	
004	70.2	70.7	
005	72.0	· 71.3	
006	73.4	71.1	
007	73.4	71.3	
008	70.4	. 70.1	
009	69.6	72.0	
010	70.5	72.5	
ŎĬ Ĭ	70.7	72.5	

4.1 Tests and Inspections

Baseline electrical measurements were made and have been reported above. Visual inspection was carried out to obtain a baseline determination of presence or absence of defects. Ground continuity tests were not made, since the module had no external conductive surfaces.

4.2 Environmental Tests

Modules were subjected to the following environmental tests at JPL:

- Thermal cycling (T-50 and T-200)
- Humidity freeze (HF-10)
- Mechanical loading (M-10K)
- Hot Spot (HS-100)

These tests are described in JPL Document 5101-162 (Low-Cost Solar Array Project). Electrical performance test data is summarized in Table 4-2.

TABLE 4-2
SUMMARY OF ELECTRICAL PERFORMANCE
AFTER ENVIRONMENTAL TESTING

Module ID	Test	Output (6)	Delta (%)
SR5H-002	RCVG Pre-test	70.75 71.20	
	T-50	70.73	-0.7
	HF-10	70.93	-0.4
	M-10K	69.83	-1.9
SR 5H-003	RCVG	70.74	-
	Pre-test	70.52	-
	T-50	71.10	+0.8
	HF-10	70.97	+0.6
	M-IOK	69.97	-0.8
	T-200	69.14	-1.4
SR 5H-004	RCVG	70.72	•
	Pre-test	70.52	-
	T-50	70.27	-0.4
	HF-10	70.78	+0.4
	M-10K	68.66	-2.6
	Recheck	69.29	-1.7
•	T-200	66.87	-5.2
	Recheck	68.36	-3.1
SR 5H-005	RCVG ·	71.25	-
	Pre-test	71.34	-
SR 5H-006	RCVG	7 ϕ08	-
(Control Module)		71,34	-
k		71.50	+0.2
	•	71.17	-0.2
		71.10	-0.3
•		71.08	-0.4
	•	70.45	-1.2
		71.00	-0 . 5
•		70. 08	-1.7
		70.12	-1.7
		69.39	-2.8
		69.43	-2. 7
	Re-check	69.43	-2.7
		70.95	-0.5
		70.43	-0.9
•		70.45	-1.2
		70.70	-0. <i>5</i>
	· · · · · · · · · · · · · · · · · · ·	70.86	-0.7

TABLE 4-2 (Continued)

Module ID	Test	Output (6)	Delta (%)
SR5H-007	RCVG	71.34	
	Pre-test	71.34	
	T-50	71.21	-0.2
	HF-10	71.37	
	M-LOK	70.25	-1,5
	Pre-HS	70.66	1.0
	HS-100	70.43	-1.3
SR5H-008	RCVG	70.07	_
	Vendor	70.42	+0.5
	Pre-test	70.26	-
	T-50	69.33	-1.3
	Re-check	69.73	-
	HF-10		.=.
	HF-10	69.44	-1.1
SR5H-009	RCVG	71.98	-
	Vendor	69.63	-3.0
	Pre-test	72.28	-
	T-50 HF-10	70.55	-1.8
	HF-10 HF-10	69.98	-2.7
SR5H-010	R CVG	72.54	-
	Vendor	70,47	-3.0
	Pre-test	72.28	-
	T-50	71.14	-1.9
	HF-10	•	-
	HF-10	71.11	-2.3
SR 5H-011	RCVG	72.46	-
	Vendor	70.67	-2.5
	Pre-test	72.30	
4	T-50 HF-10	71.08	-1.9 -
	HF-10	70.87	-2.0

An important problem that was discovered during T-50 temperature cycling tests at JPL was delamination of the back cover. This problem was investigated in detail and found to be related to a need for priming the backs of the solar cells prior to lamination. Subsequent modules fabricated with this problem corrected passed the T-50 test and the humidity-freeze tests. The modules passed the JPL test sequence.

SECTION 5 NEW TECHNOLOGY

No reportable items of new technology have been identified in this contract.